

NOTICE INVITING QUOTATIONS

Subject: Invitation of Quotations for Construction of Shed at the Office Building

Quotations are hereby invited from interested and eligible contractors/agencies for the construction of a shed at the office building, as per the dimensions and specifications indicated in the attached drawing/details.

Interested parties may submit their quotations, clearly indicating the total estimated cost of construction, material specifications, labour charges, applicable taxes, and the time required for completion of the work.

The quotations must reach the office on or before **29 October 2026**. The quotation period shall remain open for one week, commencing from **22 October 2026**.

The work shall be executed as per the approved dimensions and specifications and subject to the terms and conditions prescribed by the office. The office reserves the right to accept or reject any or all quotations without assigning any reason.

Interested parties may contact the office for any clarification or inspection of the site, if required.

Date of Notice: 22 October 2026

Regional Institute of Cooperative Management
Sector 32 C, Chandigarh

Measurment

Name of work:- Shed work in the Institute of Regional Institute of Cooperative Management, Sector-32, Chandigarh.

item no.	Description of item	Nos.		Length (L)	Breadth/Width (B)	Height/Depth (H)	Qty.	Unit
	Date of Measurement:-							
#REF!	Earth work by mechanical / manual means in rough excavation, banking excavated earth in layers not exceeding 20cm in depth, breaking clods, watering, rolling each layer with 1/2 tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead upto 50 m and for all lift							
1.1	All kinds of soil							
	Shed Pillar	1	4	0.60	0.60	0.6	0.86	Cum
						Total	0.86	Cum
#REF!	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead							
	Shed Pillar	1	4	0.60	0.60		1.44	Sqm
						Total	1.44	Sqm
#REF!	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :							
3.1	1:2:4 (1 Cement : 2 coarse sand(zone-III) derived from natural sources : 4 graded stone aggregate 40 mm nominal size derived from natural sources).							
	Shed Pillar	1	4	0.60	0.60	0.6	0.86	Cum
						Total	0.86	Sqm
#REF!	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :							
4.1	Cement mortar 1:6 (1 cement : 6 coarse sand)							
	Back Side Wall	1	1	5.00	0.23	1.00	1.15	Cum
						Total	1.15	Cum
#REF!	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.							
5.1	Hot finished welded type tubes.							
5.1	75 mm Round Pipe							

	Shed Pillar V	1	4	3.00			12.00	Mtr
						Total:-	12.00	Mtr
	Weight @ 4.45Kg/Mtr					Total:- (A)	53.40	Kg
	50X50mm Sqr Pipe							
	Shed Top Parling	1	6	5.00			30.00	Mtr
	Kanchi	1	6	5.50			33.00	Mtr
	Side	2	3	5.50			33.00	Mtr
	Front	1	3	5.00			15.00	Mtr
		1	2	2.75			5.50	Mtr
						Total:-	116.50	Mtr
	Weight @ 3.00 Kg/Mtr					Total:- (A)	349.50	Kg
					Total:-(A+B)		402.90	Kg
#REF!	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.							
	Shed Top	1	1	5.50	5.00		27.50	Sqm
	Side	1	2	5.50	2.75		30.25	Sqm
	Front	1	1	5.00	2.75		13.75	Sqm
						Total	71.50	Sqm
#REF!	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :							
#REF!	Two or more coats on new work.							
	Shed	1	1	5.50	5.00		27.50	Sqm
						Total	27.50	Sqm